



CELLARS – BEDDING – SITE PREPARATION

Where soil type allows

- Excavate hole 500mm all-round larger than cellar - outside dimensions
- Determine finished height of cellar and excavate depth 100mm below
- Fill, screed and compact washed sand or aggregate to 100mm finished height
- Once cellar installed backfill and compact in max 500mm layers (do not contact cellar wall with vibrator)

NOTE: Cellars with 150mm walls, floor & lid - 1 to 3 & 7 Cellars with 175mm walls, floor & lid 4 – 6, 8 & 9

Total installed height – 2250 Total installation height – 2600 Height – 2225 Internal

DIMENSIONS & COST (ex GST)

	SIZE	Box PRICE	WEIGHT	Lid PRICE	WEIGHT
1	2000 x 3050	\$18,350.00	12.7	\$1,590.00	2.8
2	3050 x 3050	\$19,800.00	16.1	\$1,720.00	4.1
3	3050 x 3350	\$20,400.00	17.2	\$1,780.00	4.5
4	3050 x 4450	\$26,000.00	20.8	\$2,260.00	6.0
5	3050 x 4750	\$27,600.00	21.8	\$2,400.00	6.4
6	3350 x 4450	\$28,300.00	22.0	\$2,470.00	6.5
7	3700 x 3700	\$24,250.00	20.4	\$2,100.00	6.0
8	3700 x 5050	\$32,000.00	25.2	\$2,780.00	8.2
9	3700 x 6000	\$35,880.00	28.5	\$3,120.00	9.7



FURTHER COSTS TO FACTOR – (Approximations)

Escort Vehicle (Over 3.6m)		\$5.00 per Km
Excavation		\$35.00 m ³
Crane (Cellar sizes)	1-7	\$6,500.00
	8 & 9	\$8,000.00
Freight (Cellar sizes)	1-4 & 7	\$7.50 per Km
	5, 6 & 8, 9	\$8.50 per Km

PAYMENT TERMS

30% deposit upon placement of order with balance due upon dispatch - Photographic evidence of dispatched unit will be provided.

Documented proof of crane Audit/Site inspection MUST be provided prior to delivery.



222 Kuhlmann Road, Renmark, South Australia

PH: 08 8586 6931 FAX: 08 8586 4424 EMAIL: info@rustonengineers.com.au



STOCK GRIDS

NOTE:

Stock Grids

\$7,500.00 + GST + Freight per pair
(Pair = 2 X 1800x1500x480)

P.O. Box 1, Renmark, South Australia, 5341

WEB: www.hytekconcreteproducts.com.au